




TOP VIEW 1:10




รายละเอียดการเสริมเหล็ก 1:20



จางจะบายน้ำพร้อมฝาค.ด.ด. 1:10




FRONT VIEW 1:10




SIDE VIEW 1:10

1. PUSH-TO-OPEN LOCKABLE DEVICE, KEYED ALIKE, FINISHED CHROMED.
2. SAFETY CLASS 5 MM. THICK DOOR PANEL.
3. RECESSED TYPE CABINET MADE OF 18 GAUGE STEEL WITH STAINLESS STEEL/STEEL TRIM & STAINLESS STEEL/STEEL DOORFRAME. DOOR TO BE FURNISHED WITH CONTINUOUS STAINLESS STEEL/STEEL HINGE (BRASS PIN), WITH PUSH-TO-OPEN LOCKABLE DEVICE, KEYED ALIKE. CABINET SHALL BE CLEANED & COATED WITH PHOSPHATE SOLUTION PRIOR TO BEING FINISHED WITH BAKED-ON RED PAINTING (CUMA RED).
4. STAINLESS STEEL/STEEL HINGE WITH BRASS PIN.
5. ABC DRY CHEMICAL (AMMONIUM PHOSPHATE BASE) FIRE EXTINGUISHER OF 1 LB., 15 LB. OR TO 18., AS SPECIFIED AND APPROVED TO TIS PER-0511.
6. 2 1/2" CAST BRASS WITH 300 LB. FIRE DEPT. MANGLE HOSE VALVE WITH 2 1/2" CAST BRASS INSTANTANEOUS COUPLING ADAPTOR WITH CAP & CHAIN.
7. AUTOMATIC RECESSED HOSE REEL COMPLETE SET TO BS 5174-1955 WITH 1"X100' RED RUBBER HOSE, TO BS 5167-1956 CLASS A OR B. AUTOMATIC VALVE MECHANISM SHALL BE NON CORRODED METAL (STAINLESS STEEL).
8. 1" PLASTIC ADJUSTABLE NOZZLE.
9. 1" GATE VALVE OR BALL VALVE.
10. STEEL HOSE REEL PLATE BOLTED TO CABINET.
11. 1" NIPPLE.
12. 2 1/2" NIPPLE.
13. 1" UNION.
14. REDUCING TEE 2 1/2"x1".



แปลน 1:5 บ่อตกกลิ้ง



รูปตัดบ่อตักกลีบ

[illegible]